



BRANZ Appraised
Appraisal No. 1181 [2021]

**HERMPAC ACCOYA®
VERTILINE
VERTICAL SHIPLAP
WEATHERBOARD
CAVITY SYSTEM**

Appraisal No. 1181 [2021]
Amended 18 July 2022



BRANZ Appraisals

Technical Assessments of
products for building and
construction.



Hempac

Herman Pacific Limited

PO Box 35 209
Browns Bay
Auckland
Tel: 09 421 9840
Email: technical@hermpac.co.nz
Web: www.hermpac.co.nz



BRANZ

BRANZ

1222 Moonshine Rd,
RD1, Porirua 5381
Private Bag 50 908
Porirua 5240,
New Zealand
Tel: 04 237 1170
branz.co.nz



Product

- 1.1 The Hermpac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System is a cavity-based shiplap timber weatherboard external wall cladding system for residential and light commercial type buildings where domestic construction techniques are used.
- 1.2 The system consists of vertically fixed Hermpac shiplap weatherboards, ventilated cavity battens, flashings and accessories, and is finished with a premium penetrating oil, stain or an exterior paint system to Hermpac specifications.

Scope

- 2.1 The Hermpac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System has been appraised as an external wall cladding system for buildings within the following scope:
 - the scope limitations of NZBC Acceptable Solution E2/AS1, Paragraph 1.1; and,
 - constructed with timber framing complying with the NZBC; and,
 - with a risk score of 0-20, calculated in accordance with NZBC Acceptable Solution E2/AS1, Table 2; and,
 - situated in NZS 3604 Wind Zones up to, and including, Extra High.
- 2.2 The Hermpac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System has also been appraised as an external wall cladding system for buildings within the following scope:
 - the scope limitations of NZBC Acceptable Solution E2/AS1, Paragraph 1.1; and,
 - constructed with timber framing complying with the NZBC; and,
 - situated in specific design wind pressures up to a maximum design differential ultimate limit state (ULS) of 2.5 kPa.
- 2.3 The Hermpac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System must only be installed vertically on vertical, flat surfaces.
- 2.4 The Hermpac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System is appraised for use with aluminium window and door joinery that is installed with vertical jambs and horizontal heads and sills. *[Note: The Appraisal of the Hermpac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System relies on the joinery meeting the requirements of NZS 4211 for the relevant Wind Zone or wind pressure.]*



Building Regulations

New Zealand Building Code (NZBC)

3.1 In the opinion of BRANZ, the Hermpac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System, if designed, used, installed and maintained in accordance with the statements and conditions of this Appraisal, will meet the following provisions of the NZBC:

Clause B1 STRUCTURE: Performance B1.3.1, B1.3.2 and B1.3.4. The Hermpac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System meets the requirement for loads arising from self-weight, wind, impact and creep [i.e. B1.3.3 (a), (h), (j) and (q)]. See Paragraphs 9.1-9.3.

Clause B2 DURABILITY: Performance B2.3.1 (b) 15 years and B2.3.2. The Hermpac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System meets these requirements. See Paragraphs 10.1 and 10.2.

Clause E2 EXTERNAL MOISTURE: Performance E2.3.2. The Hermpac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System meets this requirement. See Paragraphs 14.1-14.5.

Clause F2 HAZARDOUS BUILDING MATERIALS: Performance F2.3.1. The Hermpac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System meets this requirement.

Technical Specification

4.1 System components and accessories supplied by Hermpac are as follows:

Hermpac Accoya® Vertiline Vertical Shiplap Weatherboards

- Hermpac Accoya® shiplap weatherboards are manufactured from New Zealand grown radiata pine, modified by a proprietary non-toxic acetylation process.
- The weatherboard lap and rebate profiles are in accordance with NZS 3617 and BRANZ Bulletin No. 411. The weatherboards are minimum 18 mm thick and are available in a range of widths and face profiles. They are supplied in random lengths up to 4.8 m. Lengths outside of the general specification may be available by special contract.
- Refer to the Appraisals listing on the BRANZ website for details of the Hermpac Accoya® shiplap weatherboard profiles covered by this Appraisal. *[Note: This Appraisal is only valid when weatherboards are supplied by Hermpac.]*

Accessories

- **Hermpac external corner mouldings** - selected Hermpac 'Smart Corner' series of profiled external corner moulds and custom two piece corners HP322A/B and HP328A/B.
- **Hermpac internal corner mouldings** - selected Hermpac 'Smart Corner' series of profiled internal corner moulds.
- **Hermpac cover boards** - Hermpac cover boards HP201 and HP202.
- **Hermpac eaves moulding** - selected Hermpac bevelled profiles including HP32 and HP33.
- **Hermpac scribes** - 10 mm wide x 40 mm and 60 mm, 17 mm wide x 40 mm and 60 mm scribes with bevelled or radiused edges supplied in 1.83 m lengths and longer.

[Note: All timber accessories are manufactured from Accoya®.]

- **Hermpac J mould flashing** - an optional Grade 316 stainless steel J-shaped flashing to cap the ends of the weatherboards at window and door jambs.
- **Vertibat cavity battens** - 45 x 20 mm [V1], 45 x 40 mm [V3], 45 x 45 mm [V5], 70 x 20 mm [V2], 70 x 40 mm [V4] or 70 x 45 mm [V6] radiata pine battens treated to Hazard Class H3.1 or H3.2. Vertibat cavity battens 45 x 18 mm [V8 and V9] are available in Western Red Cedar. The top and bottom edges are bevelled with a slope. The front and back face of the batten is grooved with 20 mm wide x 5 mm deep rebates at 100 mm centres. The grooves are offset on each face. Refer to BRANZ Appraisal No. 1189.
- **Vertibat cavity batten fixings [for 40 or 45 mm thick battens when fixed to studs only]** - 12 g x 65 mm long Grade 304 or 316 stainless steel screws [for 40 mm battens] and 12 g x 75 mm long Grade 304 or 316 stainless steel screws [for 45 mm battens].



- **Hermpac Accoya® shiplap weatherboard nail fixings [for Vertibat battens fixed to dwangs]** - Grade 316 stainless steel annular grooved Hermpac crown head, rose head, flat head or jolt head nails. The nail shank must be minimum 3.25 mm diameter and the length must allow minimum 30 mm penetration [35 mm for jolt head] of the wall frame.
 - **Hermpac Accoya® shiplap weatherboard nail fixings [for 40 or 45 mm thick Vertibat battens fixed to studs only]** - Grade 316 stainless steel annular grooved Hermpac crown head, rose head, flat head or jolt head nails. The nail shank must be minimum 2.8 mm diameter and the length must allow minimum 30 mm penetration [35 mm for jolt head] of the Vertibat batten.
 - **Hermpac Accoya® shiplap weatherboard screw fixings** - Grade 316 stainless steel starcap screws to give a minimum 21 mm penetration of wall framing or structural batten.
 - **Hermpac clinch nails** - 27 x 2 mm, 40 x 2 mm or 50 x 2 mm Grade 316 stainless steel annular grooved nails with an off-set flat head.
 - **Hermpac cover board fixings** - 50 x 2.8 mm Grade 316 stainless steel annular grooved Hermpac crown head, rose head, flat head or jolt head nails.
 - **Hermpac scriber fixings** - Grade 316 stainless steel annular grooved nails.
 - **Hermpac cavity closure strip** - Grade 316 stainless steel, punched with 3-5 mm diameter holes or slots complying with NZBC Acceptable Solution E2/AS1, Paragraph 9.1.8.3.
 - **Flashings** - Grade 316 stainless steel, including external corner flashings and internal corner flashings. Refer to the Hermpac Technical Literature for sizing requirements.
- 4.2 Accessories used with the Hermpac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System, which are supplied by the building contractor are:
- **Flexible wall underlay** - building paper complying with NZBC Acceptable Solution E2/AS1, Table 23, or breather-type membranes covered by a valid BRANZ Appraisal for use as wall underlays.
 - **Flexible wall underlay support** - polypropylene strap, 75 mm galvanised mesh, galvanised wire, or additional vertical battens for securing the flexible wall underlay in place and preventing bulging of the bulk insulation into the drainage cavity. *[Note: Mesh and wire galvanising must comply with AS/NZS 4534.]*
 - **Rigid wall underlay** - plywood or fibre cement sheet complying with NZBC Acceptable Solution E2/AS1, Table 23, or rigid sheathing covered by a valid BRANZ Appraisal for use as rigid air barrier systems.
 - **Flexible sill and jamb flashing tape** - flexible flashing tapes complying with NZBC Acceptable Solution E2/AS1, Paragraph 4.3.11, or flexible flashing tapes covered by a valid BRANZ Appraisal for use around window and door joinery openings.
 - **Window and door trim cavity air seal** - air seals complying with NZBC Acceptable Solution E2/AS1, Paragraph 9.1.6, or self-expanding, moisture cure polyurethane foam air seals covered by a valid BRANZ Appraisal, suitable for use around window, door and other wall penetration openings.
 - **Vertibat cavity batten fixings [18-20 mm thick batten]** - 40 x 2.5 mm flat head hot-dip galvanised nails or 50 x 2.87 mm hot-dip galvanised gun nails to temporarily fix the battens in place prior to installation of the cladding. Stainless steel finishing brads or nails can also be used.
 - **Vertibat cavity batten fixings [40 or 45 mm thick battens when fixed to nogs/dwangs]** - 60 x 2.8 mm flat head hot-dip galvanised nails or 60 x 2.87 mm hot-dip galvanised gun nails to temporarily fix the battens in place prior to installation of the cladding. Stainless steel finishing brads or nails can also be used.
 - **Cavity closure strip** - uPVC punched with 3-5 mm diameter holes or slots complying with NZBC Acceptable Solution E2/AS1, Paragraph 9.1.8.3.
 - **Flashings** - including horizontal inter-storey joint flashing, balustrade and parapet saddle flashing, and balustrade, parapet cap flashings and other custom flashings. Refer to the Hermpac Technical Literature for material compatibility requirements.
 - **Joinery head flashings** - as supplied by the joinery manufacturer or contractor. Refer to the Hermpac Technical Literature for compatibility requirements.
 - **Flexible sealant** - sealant complying with NZBC Acceptable Solution E2/AS1, or sealant covered by a valid BRANZ Appraisal for use as a weather sealing sealant for exterior use. Hermpac recommend the use of approved Soudal or Sika products.



Finishing System Specification - Oil or Stain Finish

- For oil or stain finish, Hermpac Accoya® shiplap weatherboards are generally supplied prefinished via Machinecoat with one coat of oil or stain. Any site-cut surfaces and ends must be sealed as per the Technical Literature. At least one further coat of exterior grade quality oil or oil-based penetrating stain must be used over the front face of the Hermpac Accoya® shiplap weatherboards to protect the weatherboards and give the desired finish colour to the exterior walls.
- Where the weatherboards are supplied uncoated, the back, face, ends and edges must be sealed with an exterior grade oil or oil-based penetrating stain prior to installation.
- All exposed edges, including top edges at sills and all bottom edges of Hermpac Accoya® shiplap weatherboards and timber accessories must be finished with at least two coats of oil or stain to protect the weatherboards and give the desired finish colour to the exterior walls. The oil or stain must be recommended for use as a wall cladding oil or stain with Accoya® by the coating manufacturer and must be applied in accordance with the coating manufacturer's instructions. Proprietary oil or stain systems have not been assessed and are therefore outside the scope of this Appraisal. *[Note: Hermpac recommends the use of oils and oil-based stains manufactured by Resene and WoodX.]*

Finishing System Specification – Paint Finish

- For paint finish, Hermpac Accoya® shiplap weatherboards are generally supplied prefinished with calcium carbonate-free primer and undercoat. Any site-cut surfaces and ends must be sealed as per the Technical Literature.
- Where weatherboards are supplied unprimed, the back, face, ends and edges must be primed, prior to installation, in accordance with the Hermpac Technical Literature.
- All exposed edges, including top edges at sills and all bottom edges of Hermpac Accoya® shiplap weatherboards and timber accessories must be finished with at least two coats of an exterior grade paint complying with any of Parts 7, 8, 9 or 10 of AS 3730 to protect the weatherboards and give the desired finish colour to the exterior walls. The paint must be recommended for use as a wall cladding paint for Accoya® by the coating manufacturer and must be applied in accordance with the coating manufacturer's instructions. Proprietary paint systems have not been assessed and are therefore outside the scope of this Appraisal. Contact Hermpac for specific information on suitable paint light reflectance values for use with Accoya®. *[Note: Hermpac recommends the use of paints manufactured by Resene.]*

Handling and Storage

- 5.1 Handling and storage of all materials supplied by Hermpac or the building contractor, whether on-site or off-site, is under the control of the building contractor. Hermpac Accoya® shiplap weatherboards and mouldings must be stacked flat and true, clear of the ground by a minimum of 150 mm and supported on dry and clean timber bearers at maximum 900 mm centres. They must be kept dry at all times, either by storing within an enclosed building, or when stored externally, an additional secondary cover to the plastic wrapping is required. Water must not penetrate the stack. Care must be taken to avoid damage to edges, ends and the weatherboard surfaces.
- 5.2 Accessories must be stored so they are kept clean, dry and undamaged. All accessories must be used within the maximum storage period recommended by the manufacturer.



Technical Literature

- 6.1 This Appraisal must be read in conjunction with:
- Hermpac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System Installation Specifications, May2022V2.
 - Vertiline Vertical Shiplap Weatherboard Cavity System Random Width and Depth, Accoya Construction Drawings, Version 1.0, dated 1 Nov 2021, all drawing referenced in VA-RWD-000 and VA-RWD-001, dated 01/11/2021.
 - VertiLine Vertical Shiplap Weatherboard Cavity System, Accoya Construction Drawings, Version 1.0, dated 1 Nov 2021, all drawings referenced in HA-SHIP-000 and HA-SHIP-001, both dated 1/11/2021.
 - VertiLine Vertical Shiplap Weatherboard 40-45 mm Cavity System, Accoya Construction Drawings, Version 1.0, dated 1 Nov 2021, all drawings referenced in HA-SHIP40-000 and HA-SHIP40-001, both dated 1/11/2021.
- 6.2 All aspects of design, use, installation and maintenance contained in the Technical Literature and within the scope of this Appraisal must be followed.

Design Information

Framing

Timber Treatment

- 7.1 Timber wall framing behind the Hermpac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System must be treated as required by NZBC Acceptable Solution B2/AS1.

Timber Framing

- 7.2 Timber framing must comply with NZS 3604 for buildings or parts of buildings within the scope limitations of NZS 3604. Buildings or parts of buildings outside the scope of NZS 3604 must be to a specific design in accordance with NZS 3603 and AS/NZS 1170. Where specific design is required, the framing must be of at least equivalent stiffness to the framing provisions of NZS 3604. In all cases, studs must be at maximum 600 mm centres. Where Vertibat cavity battens are fixed to dwangs, the dwangs must be fitted flush between the studs at 400 mm to maximum 600 mm centres. **If dwangs are at greater than 480 mm centres, a job specific sign-off by Hermpac is required.** Where interior linings compliant with NZS 3604, Section 12 are installed directly to the interior face of the wall framing, and Vertibat cavity battens are structurally fixed to studs in accordance with Paragraph 17.3 of this Appraisal, dwangs are not required. Refer to NZS 3604, Section 8.5.4 for further information.
- 7.3 Additional framing may be required at soffits, internal and external corners, and window and door openings for the support and fixing of cavity battens and the Hermpac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System.
- 7.4 Timber wall framing behind where weatherboards are joined over a cavity batten must be nominal 50 mm thickness [i.e. 45 mm minimum finished thickness].
- 7.5 Timber wall framing must have a maximum moisture content of 24% at the time of the cladding application. *[Note: If Hermpac Accoya® vertical shiplap weatherboards are fixed to framing with a moisture content of greater than 24%, problems may occur at a later date due to excessive timber shrinkage.]*

General

- 8.1 When the Hermpac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System is used for specifically designed buildings up to 2.5 kPa design differential ULS wind pressure, only the weathertightness aspects of the cladding and maximum framing centres are within the scope of this Appraisal. All other aspects of the building need to be specifically designed and are outside the scope of this Appraisal.



- 8.2 Punchings in the cavity vent strip must provide a minimum ventilation opening area of 1,000 mm² per lineal metre of wall, in accordance with the requirements of NZBC Acceptable Solution E2/AS1, Paragraph 9.1.8.3 b). *[Note: Vertibat cavity battens can be used to provide vermin proofing at the bottom of the cavity.]*
- 8.3 The ground clearance to finished floor levels as set out in NZS 3604 must be adhered to at all times. At ground level, paved surfaces, such as footpaths, must be kept clear of the bottom edge of the cladding system by a minimum of 100 mm, and unpaved surfaces by 175 mm, in accordance with the requirements of NZBC Acceptable Solution E2/AS1, Table 18.
- 8.4 At balcony, deck or roof/wall junctions, the bottom edge of the Herculac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System must be kept above the top surface of any adjacent roof flashing by a minimum of 35 mm, in accordance with NZBC Acceptable Solution E2/AS1, Paragraph 9.1.3.
- 8.5 All external walls of buildings must have barriers to airflow in the form of interior linings with all joints stopped for Wind Zones up to, and including, Very High, and rigid underlays for buildings in the Extra High Wind Zone and specifically designed buildings up to 2.5 kPa design differential ULS wind pressure. Unlined gables and walls must incorporate a rigid sheathing or an air barrier which meets the requirements of NZBC Acceptable Solution E2/AS1, Table 23. For attached garages, wall underlays must be selected in accordance with NZBC Acceptable Solution E2/AS1, Paragraph 9.1.3.4.
- 8.6 Where rigid underlays are used, the weatherboard fixing lengths must be increased by a minimum of the thickness of the underlay.
- 8.7 Where the system abuts other cladding systems, designers must detail the junction to meet their own requirements and the performance requirements of the NZBC. Details not included within the Technical Literature have not been assessed and are outside the scope of this Appraisal.

Inter-storey Junctions

- 8.8 Inter-storey drained joints must be constructed in accordance with the Technical Literature. Inter-storey drained joints must be provided to limit continuous cavities to the lesser of 2-storeys or 7 m in height, in accordance with the requirements of NZBC Acceptable Solution E2/AS1, Paragraph 9.1.9.4 b).

Structure

Mass

- 9.1 The mass of the Herculac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System is less than 30 kg/m². The system is therefore considered a lightweight cladding in terms of NZS 3604.

Impact Resistance

- 9.2 The Herculac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System has good resistance to impact loads likely to be encountered in normal residential use. The likelihood of impact damage to the system when used in light commercial situations should be considered at the design stage, and appropriate protection such as the installation of bollards and barriers should be considered for vulnerable areas.

Wind Zones

- 9.3 The Herculac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System is suitable for use in all Wind Zones of NZS 3604, up to, and including, Extra High where buildings are designed to meet the requirements of NZBC Acceptable Solution E2/AS1, Paragraph 1.1, or up to 2.5 kPa design differential ULS wind pressure where buildings are specifically designed.



Durability

Serviceable Life

- 10.1 Hermpac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System installations will meet the durability requirements of the NZBC, and are expected to have a serviceable life of at least 15 years, provided the system is maintained in accordance with this Appraisal, and the Hermpac Accoya® shiplap weatherboards are continuously protected by an oil, stain or paint finish. *[Note: For oil, stain or paint finished weatherboards, this Appraisal only covers durability with regards to structural and weathertightness performance. It does not cover appearance, which may deteriorate significantly, especially when proper and regular maintenance is not carried out.]*
- 10.2 Microclimatic conditions, including geothermal hot spots, industrial contamination and mild corrosive atmospheres, and contamination from agricultural chemicals or fertilisers can convert mildly corrosive atmosphere into aggressive environments for fasteners. The fixing of weatherboards in areas subject to microclimatic conditions requires specific design in accordance with NZS 3604, Paragraph 4.2.4, and is outside the scope of this Appraisal.

Maintenance

- 11.1 Regular maintenance is essential to ensure the performance requirements of the NZBC are continually met and to ensure the maximum serviceability of the system.
- 11.2 Regular cleaning [at least annually] of the oil, stain or paint coating is required to remove grime, dirt and organic growth, and to maximise the life and appearance of the coating. Grime may be removed by brushing with a soft brush, warm water and detergent.
- 11.3 Recoating of the oil or stain finish will be necessary throughout the life of the cladding system. Recoating must be carried out every 2-3 years, on average, in accordance with the oil or stain manufacturer's instructions. Recoating will be required more frequently on exposed northern and western facing walls. When recoating, care must be taken to ensure bottom edges and shiplap edges are well covered and penetrated with the oil or stain.
- 11.4 Recoating of the paint finish will be necessary throughout the life of the cladding system. Repainting must be carried out every 7-10 years, on average, in accordance with the paint manufacturer's instructions. When repainting, care must be taken to ensure bottom edges and shiplap edges are well covered with the paint.
- 11.5 Annual inspections must be made to ensure that all aspects of the cladding system, including flashings and joints, remain in a weatherproof condition. Any damaged areas or areas showing signs of deterioration, which would allow water ingress, must be repaired immediately. Sealant, oil, stain or paint coatings, flashings or the weatherboards must be repaired in accordance with the relevant manufacturer's instructions.
- 11.6 Minimum ground clearances as set out in this Appraisal and the Technical Literature must be maintained at all times during the life of the system. *[Note: Failure to adhere to the minimum ground clearances given in this Appraisal and the Technical Literature will adversely affect the long term durability of the Hermpac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System.]*

Prevention of Fire Occurring

- 12.1 Separation or protection must be provided to the Hermpac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System from heat sources such as fireplaces, heating appliances, flues and chimneys. Part 7 of NZBC Verification Method C/VM1 and Acceptable Solution C/AS1, and NZBC Acceptable Solution C/AS2 provide methods for separation and protection of combustible materials from heat sources.



Fire Affecting Areas Beyond the Fire Source

Vertical Fire Spread

- 13.1 This Appraisal only covers buildings 10 m or less in height. NZBC Functional Requirement C3.2 identifies that external vertical fire spread to upper floors only needs be considered for buildings with a building height greater than 10 m. Control of external vertical fire spread is therefore outside the scope of this Appraisal.

Horizontal Fire Spread

- 13.2 The Herculac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System has not been assessed for a peak heat release or total heat released rating and therefore cannot be used within 1 m of the relevant boundary or Risk Group SI Buildings.
- 13.3 Refer to NZBC Acceptable Solutions C/AS1 and C/AS2 and NZBC Verification Method C/VM2 for fire resistance rating and control of external fire spread requirements for external walls.

External Moisture

- 14.1 The Herculac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System, when installed in accordance with this Appraisal and the Technical Literature, will prevent the penetration of moisture that could cause undue dampness or damage to building elements. The system incorporates a primary and secondary means of weather-resistance (first and second line of defence) against water penetration by separating the cladding from the external wall frame with a minimum 18 mm drained cavity.
- 14.2 The cavity must be sealed off from the roof and subfloor space to meet code compliance with NZBC Clause E2.3.5.
- 14.3 The Herculac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System allows excess moisture present at the completion of construction to be dissipated without permanent damage to building elements to meet code compliance with NZBC Clause E2.3.6.
- 14.4 The details given in the Technical Literature for weather sealing are based on the principle of having a first and second line of defence against moisture entry for all joints, penetrations and junctions. The ingress of moisture must be excluded by detailing joinery and wall interfaces as shown in the Technical Literature. Weathertightness details that are developed by the designer are outside the scope of this Appraisal, and are the responsibility of the designer for compliance with the NZBC.
- 14.5 The Herculac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System, where there is a designed cavity drainage path for moisture that penetrates the cladding, does not reduce the requirements for junctions, penetrations, etc. to remain weather-resistant.

Internal Moisture

- 15.1 Buildings must be constructed with an adequate combination of thermal resistance and ventilation, and space temperature must be provided to all habitable spaces, bathrooms, laundries and other spaces where moisture may be generated or may accumulate.

Water Vapour

- 15.2 The Herculac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System is not a barrier to the passage of water vapour, and when installed in accordance with this Appraisal, will not create a risk of moisture damage resulting from condensation.

Installation Information

Installation Skill Level Requirement

- 16.1 All design and building work must be carried out in accordance with the Herculac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System Technical Literature and this Appraisal by competent and experienced tradespersons conversant with the Herculac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System. Where the work involves Restricted Building Work (RBW), this must be completed by, or under the supervision of, a Licensed Building Practitioner (LBP) with the relevant License Class.



Hermpac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System Installation

Wall Underlay and Flexible Sill and Jamb Tape Installation

17.1 The selected wall underlay and flexible sill and jamb tape system must be installed by the building contractor in accordance with the underlay and tape manufacturer's instructions, prior to the installation of the cavity battens and the rest of the Hermpac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System. Flexible wall underlay must be installed horizontally and be continuous around corners. Underlay must be lapped 75 mm minimum at horizontal joints and 150 mm minimum over studs at vertical joints. Generic rigid wall underlay materials must be installed in accordance with NZBC Acceptable Solution E2/AS1 and be overlaid with a flexible wall underlay. Proprietary systems must be installed in accordance with the manufacturer's instructions. Particular attention must be paid to the installation of the wall underlay and sill and jamb tapes around window and door openings to ensure a continuous seal is achieved and all exposed wall framing in the opening is protected.

Vertibat Cavity Batten Installation [to dwangs]

17.2 Vertibat cavity battens must be installed horizontally over the wall underlay to the wall framing [dwangs] at 400-600 mm centres. **If dwangs are at greater than 480 mm, a job specific sign-off from Hermpac is required.** The battens must be installed with the top edge sloping away from the wall underlay towards the back of the weatherboards. The cavity battens are temporarily fixed in place with the fasteners defined in the Technical Specification section of this Appraisal, prior to installation of the cladding.

Vertibat Cavity Batten Installation [to studs]

17.3 40 or 45 mm thick Vertibat cavity battens must be installed horizontally over the wall underlay to the wall framing [studs] at maximum 600 mm centres. In NZS 3604 Very High and Extra High Wind Zones and for specific design differential wind pressures above Extra High and up to 2.5 kPa, the maximum stud spacing is 400 mm. The Vertibat cavity battens are installed horizontally at 400-600 mm centres up the studs. **If battens are at greater than 480 mm, a job specific sign-off from Hermpac is required.** The battens must be installed with the top edge sloping away from the wall underlay towards the back of the weatherboards. The cavity battens must be fixed in place with one 12 g Grade 304 or 316 stainless steel screw at each stud crossing [maximum 600 mm centres]. The screws must penetrate minimum 25 mm into the framing.

Hermpac Accoya® VertiLine Vertical Shiplap Weatherboard Installation

- 17.4 Hermpac Accoya® shiplap weatherboards may be cut on-site by power or hand saw. Holes and cut-outs may be formed by using a hole saw.
- 17.5 Hermpac Accoya® shiplap weatherboards must be dry prior to installation.
- 17.6 Before the weatherboards are installed, the corner detail must be prepared to suit the selected option, e.g. external box corner, external corner moulding etc. The correct sized Grade 316 stainless steel flashings must be installed before commencing weatherboard fixing, and the cavity closure must be installed continuously around the bottom of the cavity.
- 17.7 During installation of Hermpac Accoya® Shiplap weatherboards, fresh cut surfaces and ends must be sealed in accordance with the Hermpac Technical Literature.
- 17.8 Hermpac Accoya® shiplap weatherboards must be installed starting at the corner of the wall section being clad. The first weatherboard must be installed plumb to assist with the installation of subsequent weatherboards. The weatherboards must overhang the bottom plate by a minimum of 50 mm. The weatherboards should be installed with the lap facing away from the prevailing winds.
- 17.9 Immediately prior to installing the weatherboards over the internal and external corner flashings, a continuous bead of sealant must be applied to the face of the flashing along the fixing line.
- 17.10 Hermpac Accoya® Shiplap weatherboards must be overlapped by 25 mm, with an expansion gap of 2 mm at the overlap. The underlying edge of the weatherboard lap is restrained using the Hermpac clinch nails at every cavity batten. Laps and weatherboard faces must not be pinned or fixed with clinch nails.



- 17.11 The weatherboards must be fixed in full lengths where possible. Where joints are unavoidable, scarf the weatherboard at 30° over a cavity batten, coat cut ends, apply sealant and fix with one fixing through the overlapping board either side of the scarf joint.

Nail-Fixing Weatherboards

- 17.12 Hermpac Accoya® shiplap weatherboards must be pre-drilled with a hole diameter slightly smaller than that of the nail. Each weatherboard is to be fixed with one nail per board at every cavity batten.
- 17.13 For nail-fixing of the weatherboards, Grade 316 stainless steel annular grooved Hermpac crown head, rose head, flat head or jolt head nails must be used. The nail length must allow minimum 30 mm penetration [35 mm for jolt head] of the timber framing or structurally fixed cavity batten. Note that jolt head nails are for paint finish only.
- 17.14 Fixings must be located 30-35 mm in from the weatherboard lap and a minimum of 32 mm from the end of the board. Crown head, rose head or flat head nails must finish flush onto the surface of the weatherboard, not into or below the surface. Nails must be installed with a slight upslope to reduce capillary draw. Jolt head nails must be punched a maximum of 2 mm beneath the surface of the board.

Screw Fixing Weatherboards

- 17.15 Hermpac Accoya® shiplap weatherboards must be pre-drilled with a hole diameter slightly smaller than that of the screw. Each weatherboard is to be fixed with one screw per board at every cavity batten.
- 17.16 When fixing the Hermpac Accoya® shiplap weatherboards with screws, Grade 316 stainless steel Hermpac starcap screws must be used. The length of the screws must allow a minimum 21 mm embedment into the framing timber or structurally fixed cavity batten.
- 17.17 The fixing must be located 30-35 mm in from the weatherboard lap and a minimum of 32 mm from the end of the board. The base of the screw head must finish flush onto the surface of the weatherboard, not into or below the surface.

Aluminium Joinery Installation

- 17.18 Aluminium joinery and associated head flashings must be installed by the building contractor in accordance with the Technical Literature. A 7.5-10 mm nominal gap must be left between the joinery reveal and the wall framing so a PEF rod and air seal can be installed after the joinery has been secured in place. Where metal components come into contact with the exposed face of the Accoya®, check the Technical Literature to confirm if a bond break or separation barrier is required.

Finishing

- 17.19 The application of the oil or stain finish must be in accordance with the coating manufacturer's instructions.
- 17.20 With a paint finish, to prevent swelling of the weatherboard around punched fixings, the fixing must be filled immediately, or alternatively the weatherboard and the head of the fixing must be primed with a calcium carbonate-free timber primer. The paint coating manufacturer's instructions must be followed at all times for the application of the paint finish. Hermpac Accoya® Shiplap weatherboards must be painted as soon as practicable following fixing, and must be clean and dry before commencing. If the Hermpac Accoya® Shiplap weatherboards are exposed to the weather for more than 2 months, they must be reprimed with one coat of calcium carbonate-free primer prior to the application of the finishing coats. Allow the recommended drying time between coats and follow the temperature limitations for application.

Inspection

- 17.21 The Technical Literature must be referred to during the inspection of Hermpac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System installations.



Health and Safety

- 18.1 Cutting of Hermpac Accoya® Shiplap weatherboards must be carried out in well ventilated areas, and dust masks, eye and hearing protection must be worn.
- 18.2 Safe use and handling procedures for the components that make up the Hermpac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System are provided in the relevant manufacturer's Technical Literature.

Basis of Appraisal

The following is a summary of the technical investigations carried out:

Tests

- 19.1 The following testing has been completed by BRANZ:
 - BRANZ expert opinion on NZBC Clause E2 code compliance for the Hermpac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System is based on testing and evaluation of all details within the scope and as stated within this Appraisal.
 - Fastener pull through testing. BRANZ determined design wind suction pressures, and by comparing these pressures with AS/NZS 1170 pressure coefficients, the fixing requirements were determined for timber-framed walls.

Other Investigations

- 20.1 Structural and durability opinions have been provided by BRANZ technical experts.
- 20.2 The performance of timber weatherboard wall cladding products in New Zealand has been considered, including the structural and durability performance, and non-hazardous nature.
- 20.3 Site inspections have been carried out by BRANZ to assess the practicability of installation.
- 20.4 The Technical Literature for the Hermpac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System has been examined by BRANZ and found to be satisfactory.

Quality

- 21.1 The manufacture of Hermpac Accoya® Shiplap weatherboards has been examined by BRANZ, including methods adopted for quality control. Details regarding the quality of the materials used were obtained by BRANZ and found to be satisfactory.
- 21.2 The quality of materials, components and accessories supplied by Hermpac is the responsibility of Hermpac.
- 21.3 Quality of installation on-site of components and accessories supplied by Hermpac and the building contractor is the responsibility of the installer.
- 21.4 Designers are responsible for the building design, and building contractors are responsible for the quality of installation of framing systems and joinery, wall underlays, flashing tapes, air seals, cavity battens and the Hermpac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System in accordance with the instructions of Hermpac.
- 21.5 Building owners are responsible for the maintenance of the Hermpac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System in accordance with the instructions of Hermpac.



BRANZ Appraised
Appraisal No. 1181 [2021]

BRANZ Appraisal
Appraisal No. 1181 [2021]
18 November 2021

HERMPAC ACCOYA®
VERTILINE VERTICAL SHIPLAP
WEATHERBOARD CAVITY SYSTEM



BRANZ

Sources of Information

- AS 3730 Parts 7, 8, 9 and 10 - Guide to the properties of paints for buildings.
- AS/NZS 1170:2002 Structural design actions.
- AS/NZS 4534:2006 Zinc and zinc/aluminium-alloy coatings on steel wire.
- BRANZ Appraisal No. 1189 Herpac Cedar Horizontal Cavity Battens.
- BRANZ Bulletin No. 411, Recommended timber cladding profiles, April 2001.
- NZS 3602:2003 Timber and wood-based products for use in building.
- NZS 3603:1993 Timber structures standard.
- NZS 3604:2011 Timber-framed buildings.
- NZS 3617:1979 Specification for profiles of weatherboards, fascia boards and flooring.
- NZS 4211:2008 Specification for performance of windows.
- Ministry of Business, Innovation and Employment Record of amendments - Acceptable Solutions, Verification Methods and handbooks.
- The Building Regulations 1992.

Amendments

Amendment No.1, dated 18 July 2022

This Appraisal has been amended to adjust the minimum thickness of the weatherboards.



BRANZ Appraised
Appraisal No. 1181 [2021]

BRANZ Appraisal
Appraisal No. 1181 [2021]
18 November 2021

HERMPAC ACCOYA®
VERTILINE VERTICAL SHIPLAP
WEATHERBOARD CAVITY SYSTEM



In the opinion of BRANZ, the **Hermpac Accoya® VertiLine Vertical Shiplap Weatherboard Cavity System** is fit for purpose and will comply with the Building Code to the extent specified in this Appraisal provided it is used, designed, installed and maintained as set out in this Appraisal.

The Appraisal is issued only to **Herman Pacific Limited**, and is valid until further notice, subject to the Conditions of Appraisal.

Conditions of Appraisal

1. This Appraisal:
 - a) relates only to the product as described herein;
 - b) must be read, considered and used in full together with the Technical Literature;
 - c) does not address any Legislation, Regulations, Codes or Standards, not specifically named herein;
 - d) is copyright of BRANZ.
2. **Herman Pacific Limited:**
 - a) continues to have the product reviewed by BRANZ;
 - b) shall notify BRANZ of any changes in product specification or quality assurance measures prior to the product being marketed;
 - c) abides by the BRANZ Appraisals Services Terms and Conditions;
 - d) warrants that the product and the manufacturing process for the product are maintained at or above the standards, levels and quality assessed and found satisfactory by BRANZ pursuant to BRANZ's Appraisal of the product.
3. BRANZ makes no representation or warranty as to:
 - a) the nature of individual examples of, batches of, or individual installations of the product, including methods and workmanship;
 - b) the presence or absence of any patent or similar rights subsisting in the product or any other product;
 - c) any guarantee or warranty offered by **Herman Pacific Limited**.
4. Any reference in this Appraisal to any other publication shall be read as a reference to the version of the publication specified in this Appraisal.
5. BRANZ provides no certification, guarantee, indemnity or warranty, to **Herman Pacific Limited** or any third party.

For BRANZ

Chelydra Percy

Chief Executive

Date of Issue:

18 November 2021