



## BRANZ Appraised

Appraisal No. 805 [2023]

## BONDLAST DAMP PROOF AND TANKING MEMBRANES

### Appraisal No. 805 [2023]

This Appraisal replaces BRANZ  
Appraisal No. 805 [2018]

Amended 24 May 2024



### BRANZ Appraisals

Technical Assessments of  
products for building and  
construction.

# DGL

### DGL Manufacturing Ltd T/A Bondlast

#### Construction Products

24-28 Lady Ruby Drive  
East Tamaki  
Auckland 2013

Tel: 09 267 2772

Web: [www.dglgroup.co.nz](http://www.dglgroup.co.nz)



**BRANZ**

### BRANZ

1222 Moonshine Rd,  
RD1, Porirua 5381  
Private Bag 50 908  
Porirua 5240,  
New Zealand  
Tel: 04 237 1170  
[branz.co.nz](http://branz.co.nz)



## Product

- 1.1 Bondlast Damp Proof and Tanking Membranes: Bituthene® and Preprufe®, are self-adhesive or pre-applied damp-proof membranes (DPM) and tanking membranes for basement retaining walls and floors. They are applied under floor slabs and foundations and to the exterior face of basement retaining walls to prevent liquid water or water vapour penetrating to the interior face in spaces where moisture may cause damage.
- 1.2 Bituthene® is supplied as self-adhering, polymer-rubber modified bitumen sheets and Preprufe® is supplied as multi-layered composite sheets in roll form.

## Scope

- 2.1 Bondlast Damp Proof Membrane: Bituthene® has been appraised for use as a DPM within the following scope:
  - on buildings subject to non-specific design under floor slabs complying with NZS 3604 and behind concrete masonry basement walls and under floor slabs complying with NZS 4229; and,
  - in buildings subject to specific design with substrates of in-situ or precast concrete complying with NZS 3101 or concrete masonry complying with NZS 4230 and NZS 4210; and,
  - where subsoil drainage and free draining granular backfill has been placed behind basement walls.
- 2.2 Bondlast Tanking Membrane: Preprufe® has been appraised for use as a tanking membrane within the following scope:
  - on buildings subject to specific design with substrates of in-situ or precast concrete complying with NZS 3101; and,
  - where the membrane is subject to hydrostatic pressure with the pressure not to exceed 2 bar [20 m head of water].
- 2.3 Bondlast Damp Proof and Tanking Membranes: Bituthene® and Preprufe® must be adequately protected against damage during backfilling and in service.
- 2.4 The products must be installed by Bondlast Construction Products licensed applicators.

## Building Regulations

### New Zealand Building Code (NZBC)

- 3.1 In the opinion of BRANZ, Bondlast Damp Proof and Tanking Membranes, if designed, used, installed and maintained in accordance with the statements and conditions of this Appraisal, will meet the following provisions of the NZBC:

**Clause B2 DURABILITY:** Performance B2.3.1 (a) not less than 50 years. Bondlast Damp Proof and Tanking Membranes meet this requirement. See Paragraph 9.1.

**Clause E2 EXTERNAL MOISTURE:** Performance E2.3.3. Bondlast Damp Proof and Tanking Membranes meet this requirement. See Paragraphs 11.1–11.3.

**Clause F2 HAZARDOUS BUILDING MATERIALS:** Performance F2.3.1. Bondlast Damp Proof and Tanking Membranes meet this requirement.

## Technical Specification

- 4.1 Materials supplied by Bondlast Construction Products and GCP are as follows:

- **Bituthene® 3000** is a self-adhesive, modified bituminous membrane made up of 1.4 mm rubberised asphalt and 0.1 mm cross laminated polyethylene outer face for use as a below ground DPM. It is supplied in a roll 1.5 mm thick x 1 m wide x 20 m long.
- **Bituthene® 8000** is a methane-resistant, self-adhesive, modified bituminous membrane made up of 1.4 mm rubberised asphalt and 0.1 mm cross-laminated polyethylene outer face for use as a below ground DPM used to prevent landfill gases entering buildings. It is supplied in a roll 1.5 mm thick x 1 m wide x 20 m long.
- **Preprufe® 160R Plus** is a pre-applied, multi-layered composite sheet comprising of a thick HDPE film, pressure-sensitive adhesive and a weather-resistant protective coating for use as a below ground DPM or tanking membrane. Preprufe® 160R Plus is a thinner grade for blind side, zero property line applications. It is supplied in a roll 0.8 mm thick x 1.2 m wide x 35 m long.
- **Preprufe® 300R Plus** is a pre-applied, multi-layered composite sheet comprising of a thick HDPE film, pressure-sensitive adhesive and a weather-resistant protective coating for use as a below ground DPM or tanking membrane. Preprufe® 300R Plus is a tougher grade used for horizontal applications. It is supplied in a roll 1.2 mm thick x 1.2 m wide x 30 m long.
- **Preprufe® Tape** is a pre-applied, multi-layered composite sheet comprising of a thick HDPE film pressure-sensitive adhesive, a weather-resistant protective coating and a self-adhesive underside used to detail all Preprufe® installations. It is supplied in a roll 1.2 mm thick x 100 mm wide x 15 m long.
- **Membrane Primer** is a fast-drying, cutback asphalt solution for priming all concrete surfaces. It is supplied as a black solution in 20 L cans.
- **Bituthene® B2 Primer** is an asphalt solution for priming all damp or wet surfaces. It is supplied as a black solution in 25 L cans.
- **Bituthene® Mastic** is an asphalt-based mastic used to seal membrane terminations, patches and any other details. It is supplied as a black paste in 300 ml cartridges.
- **Bituthene® Liquid Membrane LM3000** is a two-component polyurethane mastic used to seal critical areas and details. It is supplied as a 5.7 L kit.
- **Drainage Sheet NPX** is a dimpled polypropylene sheet with an adhered filter fabric for vertical and horizontal protection and drainage of waterproofing membranes. It is supplied in rolls 7 mm thick, 2 m wide and 20 m long.

## Handling and Storage

- 5.1 Handling and storage of all materials, whether on-site or off-site, is under the control of the installer. Dry storage must be provided for all products and the membranes must be protected from sunlight and ultraviolet (UV) radiation. Rolls of membrane must be stored on end.

## Technical Literature

- 6.1 This Appraisal must be read in conjunction with:
- Method Statement / Specification Bituthene 3000 April 2023.
  - Method Statement / Specification Preprufe 300R Plus April 2023.
  - Method Statement / Specification Preprufe 300R Plus & Bituthene 3000 April 2023.
- 6.2 All aspects of design, use, installation and maintenance contained in the Technical Literature and within the scope of this Appraisal must be followed.

## Design Information

### Substrate Design

#### Walls – Bituthene®

- 7.1 Substrate design must be in accordance with the NZBC to a relevant standard, such as NZS 3101 for concrete, and NZS 4229 or NZS 4230 for concrete masonry.
- 7.2 The substrate must have a surface finish that is smooth, clean and free from defects or irregularities which may damage the membrane or allow water to trap behind the membrane.

#### Control Joints

- 7.3 Where control or construction joints are formed in the substrate, Bondlast Construction Products must be consulted for use of the membranes over these joints.

#### Concrete Slab-on-ground

- 7.4 The membranes must be laid on a minimum of 75 mm thickness of site concrete or well compacted sand. The structural concrete slab placed over the membranes must be a minimum of 100 mm thick.

## Backfilling and Drainage

### Bituthene® Range

- 8.1 The membranes must be protected against damage by the placement of a protection material between the membranes and the granular fill.
- 8.2 The minimum requirement for backfilling is that a granular, free-draining material is used, with the top of the backfill capped with an impervious clay fill that may be covered with topsoil if required. The impervious capping and topsoil must slope with a minimum of 1:30 fall away from the wall.
- 8.3 A minimum 100 mm diameter subsoil perforated drainage pipe must be installed at the bottom of the wall. The pipe must be covered with a geotextile filter fabric, be laid at a minimum 1:200 fall and discharge to a drainage outlet. Provision for cleaning the pipe must also be provided.
- 8.4 Backfilling should begin as soon as possible.

### Preprufe® Range

- 8.5 As Preprufe® is a pre-applied DPM tanking membrane, on specifically designed substrates, there is no backfilling required.

## Durability

### Serviceable Life

- 9.1 Bondlast Damp Proof and Tanking Membranes are suitable DPM and tanking materials, therefore they are expected to have a serviceable life of at least 50 years, provided they are installed and maintained in accordance with this Appraisal and are continually protected from sunlight and UV radiation.

## Maintenance

- 10.1 Annual inspections must be made of the membranes top edge seal and protection, the backfill capping, and the drainage pipe to ensure all are functioning as originally designed.
- 10.2 If required, the drainage pipe must be cleared to remove any sediment or silt build-up. The slope of the backfill capping must be maintained at all times.

## External Moisture

- 11.1 Bondlast Damp Proof and Tanking Membranes, when installed in accordance with this Appraisal and the Technical Literature, will prevent water vapour (DPM) and water (tanking) from penetrating to the interior face of basement retaining walls and floors in spaces where moisture may cause damage. The membranes have a vapour flow resistance of not less than 90 MN s/g.
- 11.2 The membranes can be used to form sealed joints and to seal penetrations. The top edge of the membranes must be sealed to the wall as set out in the Technical Literature and protected.
- 11.3 Building designers must ensure junctions with other membranes, such as at the floor/wall junction, form a waterproof joint. These junctions have not been assessed and are outside the scope of this Appraisal.

## Installation Information

### Installation Skill Level Requirement

- 12.1 All design and building work must be carried out in accordance with the Bondlast Damp Proof and Tanking Membranes Technical Literature and this Appraisal. All building work must be undertaken by Bondlast Construction Products licensed applicators. Where the work involves Restricted Building Work (RBW) this must also be completed by, or under the supervision of, a Licensed Building Practitioner (LBP) with the relevant License Class.

### System Installation – Bituthene® Range

#### Substrate Preparation

- 13.1 All vertical surfaces must be checked to ensure they are dry, clean, smooth and free from sharp edges, loose or foreign materials, oil, grease or other deleterious material that may affect adhesion or may damage the membranes.

#### Priming

- 13.2 All substrates must be primed before application of the membranes. The supplier of the membranes, Bondlast Construction Products, should be contacted to confirm the most suitable primer. Application instructions for the primers are contained in the technical data sheets.

#### Membrane Installation – Walls

- 13.3 Starting at the lowest point, the membranes must be installed in accordance with the Technical Literature. Sheet edges must be overlapped a minimum of 50 mm as marked on the sheets. End laps must be a minimum of 150 mm, with upper sheets lapped over lower sheets. Internal and external corners must be reinforced with an extra layer of membrane 300 mm wide. Protection material must be installed before backfilling. Backfilling must commence immediately after the membranes are installed to ensure the membranes is not left exposed to sunlight or UV radiation.

#### Membrane Installation – Floors

- 13.4 Membranes must be installed in accordance with the Technical Literature. Sheet edges must be overlapped a minimum of 50 mm as marked on the sheets and end laps must be a minimum of 150 mm. The membranes must be inspected for damage and any damage must be repaired in accordance with the Technical Literature. The membranes must not be exposed to UV radiation for any longer than two months before the structural concrete slab is placed.

### System Installation – Preprufe® Range

#### Site Preparation

- 14.1 All surfaces are to be sound and solid to eliminate movement during concrete placement. Substrates must be regular and smooth with no gaps or voids greater than 12 mm. Grout must be used around all penetrations such as utility conduits for stability.

### Membrane Installation

- 14.2 Preprufe® membranes must be installed to all areas required to achieve a waterproof finish, in accordance with Bondlast Construction Products Technical Literature. Temperatures must be -4°C or above during installation.
- 14.3 The HDPE film must be facing the prepared substrate and the treated white coating surface facing the new concrete. The end laps must be staggered to avoid build up of layers.
- 14.4 The end laps must be accurately positioned to avoid build up of layers. Sheets must overlap the previous sheet by a minimum of 75 mm (side and end laps). The underside of the sheet must be clean, dry and free from contamination before making the overlaps.
- 14.5 Vertical lengths greater than 2.4 m must be mechanically fastened under the vertical laps at 0.6 m intervals using flat head nails or fixings suitable for the substrate. Fixings are to be placed through the lap so that the membrane lays flat to enable heavy rolling. Fixings within the sheet must be covered with a patch of Preprufe® Tape.
- 14.6 All cut ends or laps must be completed using Preprufe® Tape.
- 14.7 Concrete must be placed within 40 days.

### Inspections

- 14.8 The Technical Literature and the installation company's Quality Control sheets must be referred to during the inspection of the membrane installation.

### Health and Safety

- 15.1 Safe use and handling procedures for the membranes are provided in the Technical Literature.

## Basis of Appraisal

The following is a summary of the technical investigations carried out:

### Tests

- 16.1 The following testing of Bondlast Damp Proof and Tanking Membranes has been undertaken:
  - Tensile strength, elongation, nail tear, water vapour permeability, low temperature flexibility after heat ageing, static indentation, dynamic indentation, unrolling at low temperatures, resistance to water pressure (also tested on joints), peel resistance from concrete heat aged, resistance to sliding, tensile strength of joints, chisel impact, air leakage, shear strength of joints, water vapour transmission, tensile strength, tear resistance, watertightness and resistance to static loading.

Test methods and results have been reviewed by BRANZ and found to be satisfactory.

### Other Investigations

- 17.1 A durability opinion has been given by BRANZ technical experts.
- 17.2 Practicability of installation has been assessed by BRANZ and found to be satisfactory.
- 17.3 The Technical Literature has been examined by BRANZ and found to be satisfactory.

### Quality

- 18.1 The manufacture of the membranes and primers have not been examined by BRANZ, but details regarding the quality and composition of the materials used were obtained by BRANZ and found to be satisfactory.
- 18.2 The quality of materials supplied to the market is the responsibility of Bondlast Construction Products.
- 18.3 Quality of installation on-site is the responsibility of the Bondlast Construction Products licensed applicator.
- 18.4 Designers are responsible for the building design, and building contractors are responsible for the quality of construction of substrate systems in accordance with the instructions of Bondlast Construction Products.
- 18.5 Building owners are responsible for the maintenance of the membrane systems in accordance with the instructions of Bondlast Construction Products.

### Sources of Information

- NZS 3101:2006 Concrete structures standard.
- NZS 3604:2011 Timber-framed buildings.
- NZS 4229:2013 Concrete masonry buildings not requiring specific engineering design.
- NZS 4230:2004 Design of reinforced concrete masonry structures.
- Ministry of Business, Innovation and Employment Record of amendments - Acceptable Solutions, Verification Methods and handbooks.
- The Building Regulations 1992.

### Amendments

#### Amendment No. 1, dated 24 May 2024.

This Appraisal has been amended to update the Appraisal Holder and Appraisal name.



In the opinion of BRANZ, **Bondlast Damp Proof and Tanking Membranes** are fit for purpose and will comply with the Building Code to the extent specified in this Appraisal provided they are used, designed, installed and maintained as set out in this Appraisal.

The Appraisal is issued only to **DGL Group Ltd T/A Bondlast Construction Products**, and is valid until further notice, subject to the Conditions of Appraisal.

### Conditions of Appraisal

1. This Appraisal:
  - a) relates only to the product as described herein;
  - b) must be read, considered and used in full together with the Technical Literature;
  - c) does not address any Legislation, Regulations, Codes or Standards, not specifically named herein;
  - d) is copyright of BRANZ.
2. **DGL Group Ltd T/A Bondlast Construction Products:**
  - a) continues to have the product reviewed by BRANZ;
  - b) shall notify BRANZ of any changes in product specification or quality assurance measures prior to the product being marketed;
  - c) abides by the BRANZ Appraisals Services Terms and Conditions;
  - d) warrants that the product and the manufacturing process for the product are maintained at or above the standards, levels and quality assessed and found satisfactory by BRANZ pursuant to BRANZ's Appraisal of the product.
3. BRANZ makes no representation or warranty as to:
  - a) the nature of individual examples of, batches of, or individual installations of the product, including methods and workmanship;
  - b) the presence or absence of any patent or similar rights subsisting in the product or any other product;
  - c) any guarantee or warranty offered by **DGL Group Ltd T/A Bondlast Construction Products**.
4. Any reference in this Appraisal to any other publication shall be read as a reference to the version of the publication specified in this Appraisal.
5. BRANZ provides no certification, guarantee, indemnity or warranty, to **DGL Group Ltd T/A Bondlast Construction Products** or any third party.

For BRANZ



**Claire Falck**

Acting Chief Executive

Date of Issue:

20 July 2023