



BRANZ Appraised

Appraisal No. 877 [2025]

CLEARVUE ROOFING SYSTEM

Appraisal No. 877 [2025]

This Appraisal replaces BRANZ Appraisal No. 877 [2019]



BRANZ Appraisals

Technical Assessments of products for building and construction.



PSP Limited

PO Box 101 851

Tel: 09 415 2800

Web: www.psp.co.nz



BRANZ

BRANZ

1222 Moonshine Rd,

RD1, Porirua 5381

Private Bag 50 908

Porirua 5240,

New Zealand

Tel: 04 237 1170

branz.co.nz

Product

- 1.1 The ClearVue Roofing System is an exterior roofing system for use as porches or verandas over decks or patios or free standing, clear roofing structures.
- 1.2 The ClearVue Roofing System offers three distinct methods of installation to suit a range of applications. This includes utilising the ClearVue Span Bar as a structural rafter, fixing to timber rafters and fixing to timber purlins. Refer to Paragraph 7.3 for further information.

Scope

- 2.1 The ClearVue Roofing System is for the construction of open-sided, porch or veranda-type roof structures attached to buildings that are Risk Group SH as defined by NZBC Acceptable Solution C/AS1 and other attached or detached roof structures not subject to fire Group Number requirements.
- 2.2 The ClearVue Roofing System is designed for use in NZS 3604 Wind Zones up to, and including, Extra High, and with a minimum roof pitch of 3° and maximum roof pitch of 30°.

Building Regulations

New Zealand Building Code (NZBC)

- 3.1 In the opinion of BRANZ, the ClearVue Roofing System, if designed, installed, used and maintained in accordance with the statements and conditions of this Appraisal will meet the following provisions of the NZBC:

Clause B1 STRUCTURE: Performance B1.3.1, B1.3.2 and B1.3.4 for the relevant physical conditions of B1.3.3 being self-weight, snow, wind, and impact [i.e. B1.3.3 (a), (g), (h), and (j)]. The ClearVue Roofing System meets these requirements. See paragraphs 8.1-8.5.

Clause B2 DURABILITY: Performance B2.3.1 (b) 15 years. The ClearVue Roofing System meets these requirements. See paragraph 9.1.

Clause F2 HAZARDOUS BUILDING MATERIALS: Performance F2.3.1. The ClearVue Roofing System meets this requirement.



Technical Specification

- 4.1 Components of the ClearVue Roofing System are supplied by PSP Limited include:
- **ClearVue Sheets** - The sizes given below are stocked as standard lengths.
 - 6 mm thick acrylic panels, clear or grey in colour with dimensions of either 3,700 x 586 mm or 5,100 x 586 mm.
 - 8 mm thick acrylic panels, clear or grey in colour with dimensions of either 3,700 x 736 mm or 5,100 x 736 mm.
 - **Aluminium Extrusions** - The sizes given below are stocked as standard lengths, however lengths up to 6 m are available on indent.
 - ClearVue Glazing Bottom Rail - in 3.7 and 5.1 m lengths.
 - ClearVue Glazing Cover Rail - in 3.7 and 5.1 m lengths.
 - ClearVue Glazing Middle Rail - in 3.7 and 5.1 m lengths.
 - ClearVue F Profile - for 6 mm thick panels in 3.7 and 5.1 m lengths.
 - ClearVue F Profile - for 8 mm thick panels in 3.7 and 5.1 m lengths.
 - ClearVue Span Bar - in 3.7 and 5.1 m lengths.
 - **Aluminium Components**
 - ClearVue Glazing Spanbar End Cap - for 6 and 8 mm thick panels.
 - ClearVue Glazing Spanbar Bottom Split End Cap.
 - ClearVue Glazing Spanbar Top Split End Cap - for 6 mm thick panels.
 - ClearVue Glazing Spanbar Top Split End Cap - for 8 mm thick panels.
 - ClearVue Glazing End Cap - for 6 mm thick panels.
 - ClearVue Glazing End Cap - for 8 mm thick panels.
 - **Other Components**
 - ClearVue Glazing Gasket - in 15 and 21 m lengths.
 - ClearVue Span Bar U Bracket - 3 mm thick, grade 316 stainless steel.
 - ClearVue Span Bar Rafter Angle Bracket - 3 mm thick, grade 316 stainless steel.
 - ClearVue Foam Flashing Tape - 20 x 15 mm white, self-adhesive foam tape.
 - Butyl Rubber Tape.
 - Assorted grade 316 stainless steel fixings.
- 4.2 Components of the ClearVue Roofing System supplied by others are:
- **Flashings**
 - Flashings are folded from aluminium or galvanised steel. Refer to NZS 3604, Section 4 and NZBC Acceptable Solution E2/AS1 for material selection durability requirements if not otherwise specified.

Packaging, Handling and Storage

- 5.1 Prior to installation the ClearVue sheets should be covered and stored horizontally on a flat surface. Stacking the panels vertically is not recommended. Other components of the system should be stored in a clean, dry area until installation.

Technical Literature

- 6.1 This Appraisal must be read in conjunction with:
- ClearVue Roofing System, Typical Installation Details, dated September 2023.
 - ClearVue Roofing System - Installation Instructions for Rafters, version v250619.
 - ClearVue Roofing System - Installation Instructions for Purlins, version v140923.
 - ClearVue Roofing System - Installation Instructions for Span Bar, version v140923.
- 6.2 All aspects of design, use, installation and maintenance contained in the Technical Literature and within the scope of this Appraisal must be followed.

Design Information

General

- 7.1 The ClearVue Roofing System can be constructed with either 6 or 8 mm thick sheets. The 6 mm thick sheets are for use with a maximum ClearVue Glazing Rail or Spanbar spacing of 600 mm, and the 8 mm sheets with a maximum spacing of 750 mm.
- 7.2 The minimum roof slope for the ClearVue Roofing System is 3°, and the maximum roof pitch is 30°.
- 7.3 There are three methods of installing the system. Method A is to use the ClearVue Spanbar, which is an aluminium rafter extrusion with an integrated clamping rail for the ClearVue Sheets. Method B is to use ClearVue Glazing Rails installed on top of, and parallel with, timber rafters. Method C is to use ClearVue Glazing Rails installed on top of, and perpendicular to, timber purlins. Method C allows for the rafter spacing beneath the purlins to be different to the spacing of the ClearVue Glazing Rails.
- 7.4 Timber members used in the construction of the ClearVue Roofing System must be minimum H3.2 treated timber. ClearVue aluminium extrusions must be separated from treated timber by the butyl rubber tape or with a DPC.
- 7.5 Flashing profiles and intersection details must be to a specific weathertightness design where not detailed in the Technical Literature.

Structure

- 8.1 Tables 1 – 4 provide the maximum allowable spans for the different configurations of the ClearVue Roofing System. They include spans for NZS 3604 Wind Zones up to, and including, Extra High, and snow loading up to 1.5 kPa. *[Note: Where the rafter system is used on sites that require a design snow load of 1.5 kPa, as defined by NZS 3604, Table 15.1, the glazing rail must be fixed to the rafter at 150 mm centres.]*
- 8.2 In Tables 3 and 4 the purlins are 90 x 45 mm, MSG 8 on their flat. The fixing of the purlins to the rafters is one 14 g self-drilling type 17 screw 100 mm long. These fixings must meet the durability requirements of NZS 3604, Section 4.
- 8.3 The Spanbar brackets have been assessed as suitable for use up to the spans and in the Wind Zones given in Table 1, below.
- 8.4 Timber rafters may be connected to supporting framing using the connection details given in NZS 3604, Table 10.1 for rafters with the same loaded dimension.
- 8.5 Connection to the building and any additional structure required to support the ClearVue Roofing System should be in accordance with NZS 3604 or may require specific structural engineering design. This is outside the scope of this Appraisal.

Impact Resistance

- 8.6 The ClearVue sheets have adequate resistance to impact.

Durability

- 9.1 The components of the ClearVue Roofing System are expected to have a serviceable life of at least 15 years provided they are designed, used, installed and maintained in accordance with this Appraisal and the Technical Literature.

Maintenance

- 10.1 The ClearVue Roofing System will not normally require maintenance. However, if damage occurs to any of the components of the system then replacement can be simply carried out to ensure the ongoing integrity. Dirt, lichen, moss and other such material should be cleaned from the roofing.
- 10.2 Precautions, when maintenance is being carried out, should be in accordance with the relevant Health and Safety requirements.

Table 1: Method A, Span Bar Configuration - Maximum Allowable Spans.

Rafter	Acrylic Thickness [mm]	Max Rafter Spacing [mm]	Maximum Rafter Span [m] Wind Zone from NZS 3604:2011				
			Extra High	Very High	High	Medium	Low
Aluminium Span Bar	6	600	4.5	4.9	5.6	6	6
Aluminium Span Bar	8	750	4	4.4	5	5.4	5.4

Table 2: Method B, Glazing Bar fixed to rafter configuration - Maximum Allowable Spans.

Rafter	Acrylic Thickness [mm]	Max Rafter Spacing [mm]	Maximum Span [m] Wind Zone from NZS 3604:2011				
			Extra High	Very High	High	Medium	Low
90 x 45 Timber MSG 8	6	600	1.9	2.1	2.4	2.6	2.6
90 x 45 Timber MSG 8	8	750	1.7	1.9	2.1	2.3	2.3
140 x 45 Timber MSG 8	6	600	3	3.3	3.7	4	4
140 x 45 Timber MSG 8	8	750	2.6	2.9	3.3	3.6	3.6
190 x 45 Timber MSG 8	6	600	4	4.4	5	5.4	5.4
190 x 45 Timber MSG 8	8	750	3.6	3.9	4.5	4.8	4.8
240 x 45 Timber MSG 8	6	600	5.1	5.6	6.3	6.8	6.8
240 x 45 Timber MSG 8	8	750	4.5	5	5.7	6.1	6.1

Table 3: Method C, Glazing Bar fixed to Purlin Configurations with 6 mm thick ClearVue Sheet - Maximum Allowable Spans

Rafter Type	Max Rafter Spacing [mm]	Maximum Rafter Span and Purlin Spacing [m] Wind Zone from NZS 3604:2011					
			Extra High	Very High	High	Medium	Low
140 x 45 Timber MSG 8	600	Max Rafter Span [m]	3	3.3	3.7	4	4
		Max Purlin Spacing [m]	1	1.2	1.3	1.4	1.4
190 x 45 Timber MSG 8	600	Max Rafter Span [m]	4	4.4	5	5.4	5.4
		Max Purlin Spacing [m]	1	1.2	1.3	1.4	1.4
240 x 45 Timber MSG 8	600	Max Rafter Span [m]	5.1	5.6	6.3	6.8	6.8
		Max Purlin Spacing [m]	1	1.2	1.3	1.4	1.4
140 x 45 Timber MSG 8	750	Max Rafter Span [m]	2.6	2.9	3.3	3.6	3.6
		Max Purlin Spacing [m]	1	1.2	1.3	1.4	1.4
190 x 45 Timber MSG 8	750	Max Rafter Span [m]	3.6	3.9	4.5	4.8	4.8
		Max Purlin Spacing [m]	1	1.2	1.3	1.4	1.4
240 x 45 Timber MSG 8	750	Max Rafter Span [m]	4.5	5	5.7	6.1	6.1
		Max Purlin Spacing [m]	1	1.2	1.3	1.4	1.4

Table 4: Method C, Glazing Bar fixed to Purlin Configurations with 8 mm thick ClearVue Sheet - Maximum Allowable Spans

Rafter Type	Max Rafter Spacing [mm]	Maximum Rafter Span and Purlin Spacing [m]					
			Wind Zone from NZS 3604:2011				
			Extra High	Very High	High	Medium	Low
140 x 45 Timber MSG 8	600	Max Rafter Span [m]	3	3.3	3.7	4	4
		Max Purlin Spacing [m]	0.8	1	1.3	1.4	1.4
190 x 45 Timber MSG 8	600	Max Rafter Span [m]	4	4.4	5	5.4	5.4
		Max Purlin Spacing [m]	0.8	1	1.3	1.4	1.4
240 x 45 Timber MSG 8	600	Max Rafter Span [m]	5.1	5.6	6.3	6.8	6.8
		Max Purlin Spacing [m]	0.8	1	1.3	1.4	1.4
140 x 45 Timber MSG 8	750	Max Rafter Span [m]	2.6	2.9	3.3	3.6	3.6
		Max Purlin Spacing [m]	0.8	1	1.3	1.4	1.4
190 x 45 Timber MSG 8	750	Max Rafter Span [m]	3.6	3.9	4.5	4.8	4.8
		Max Purlin Spacing [m]	0.8	1	1.3	1.4	1.4
240 x 45 Timber MSG 8	750	Max Rafter Span [m]	4.5	5	5.7	6.1	6.1
		Max Purlin Spacing [m]	0.8	1	1.3	1.4	1.4

Prevention of Fire Occurring

- 11.1 Separation or protection must be provided to the ClearVue Roofing System from heat sources such as fireplaces, heating appliances and chimneys. Part 7 of NZBC Acceptable Solution C/AS1 and NZBC Acceptable Solution C/AS2 provide methods for separation and protection of combustible materials from heat sources.

External Moisture

- 12.1 The ClearVue Roofing System is for use over open areas. There is no weathertightness requirement for such roof systems but the ClearVue Roofing System provides an adequate weathertightness seal at glazing supports.
- 12.2 The weathertightness of structural connections to the building shall be in accordance with NZBC Acceptable Solution E2/AS1, Section 7.3. A weathertight seal of the roofing to the building should be made. Where flashings that flash under [behind] the wall cladding are used they shall be in accordance with NZBC Acceptable Solution E2/AS1 for the connection to the building. Other details are the responsibility of the designer. PSP Limited provide details for the connection of the flashing to the roofing system.

Water Supplies

- 13.1 The ClearVue Roofing System has not been assessed for roofs used for the collection of potable water.

Installation Information

Installation Skill Level Requirement

- 14.1 All design and building work must be carried out in accordance with the ClearVue Roofing System's Technical Literature and this Appraisal by competent and experienced tradespeople conversant with the ClearVue Roofing System. Where the work involves Restricted Building Work (RBW) this must be completed by, or under the supervision of, a Licensed Building Practitioner (LBP) with the relevant Licence class.

Roof Installation

- 15.1 The ClearVue Roofing System must be installed in accordance with the Technical Literature.
- 15.2 ClearVue sheets will expand and contract up to 5 mm per metre depending on the temperature. This must be allowed for when calculating the panel length.

Health and Safety

- 16.1 Care should be taken as different components of the ClearVue Roofing System may have sharp edges, especially if they have been cut. Suitable precautions should also be taken if working at heights, working with treated timber, or working with power tools.
- 16.2 At all times reliance must never be placed on the ClearVue sheets supporting loads generated by workers on a roof. These loads must always be supported with planks and the like and directly transferred to the supporting purlins, rafters and structure.

Basis of Appraisal

The following is a summary of the technical investigations carried out.

Tests

- 17.1 Structural testing of the ClearVue Roofing System was carried out by BRANZ to determine the wind face loading, span properties and impact resistance of the system.

Other BRANZ Investigations

- 18.1 Structural and durability assessments have been provided by BRANZ technical experts.
- 18.2 Observations have been made by BRANZ to assess the practicability of installation, and to examine completed installations.
- 18.3 The Technical Literature has been examined by BRANZ and found to be satisfactory.

Quality

- 19.1 The manufacture of the components of the ClearVue Roofing System has not been examined by BRANZ, but details regarding the quality and composition of the materials used were obtained by BRANZ and found to be satisfactory. BRANZ undertakes an ongoing review of product quality on an inwards goods basis.
- 19.2 The quality of the components of the ClearVue Roofing System supplied is the responsibility of PSP Limited.
- 19.3 Architect/designers are responsible for the design of the ClearVue Roofing System.
- 19.4 The roof installer is responsible for the quality of construction of the ClearVue Roofing System in accordance with the Technical Literature.
- 19.5 Building owners are responsible for the maintenance of the ClearVue Roofing System.

Sources of Information

- NZS 3604:2011 Timber-framed buildings.
- Ministry of Business, Innovation and Employment Record of amendments - Acceptable Solutions, Verification Methods and handbooks.
- The Building Regulations 1992.



In the opinion of BRANZ, the **ClearVue Roofing System** is fit for purpose and will comply with the Building Code to the extent specified in this Appraisal provided it is used, designed, installed and maintained as set out in this Appraisal.

The Appraisal is issued only to **PSP Limited**, and is valid until further notice, subject to the Conditions of Appraisal.

Conditions of Appraisal

1. This Appraisal:
 - a) relates only to the product as described herein;
 - b) must be read, considered and used in full together with the Technical Literature;
 - c) does not address any Legislation, Regulations, Codes or Standards, not specifically named herein;
 - d) is copyright of BRANZ.
2. **PSP Limited**:
 - a) continues to have the product reviewed by BRANZ;
 - b) shall notify BRANZ of any changes in product specification or quality assurance measures prior to the product being marketed;
 - c) abides by the BRANZ Appraisals Services Terms and Conditions;
 - d) warrants that the product and the manufacturing process for the product are maintained at or above the standards, levels and quality assessed and found satisfactory by BRANZ pursuant to BRANZ's Appraisal of the product.
3. BRANZ makes no representation or warranty as to:
 - a) the nature of individual examples of, batches of, or individual installations of the product, including methods and quality of work;
 - b) the presence or absence of any patent or similar rights subsisting in the product or any other product;
 - c) any guarantee or warranty offered by **PSP Limited**.
4. Any reference in this Appraisal to any other publication shall be read as a reference to the version of the publication specified in this Appraisal.
5. BRANZ provides no certification, guarantee, indemnity or warranty, to **PSP Limited** or any third party.

For BRANZ



Claire Falck

Chief Executive

Date of Issue:

25 August 2025